

TABLE OF CONTENTS

APPENDIX M UTILITY STUDIES	M-1
POTABLE WATER STUDY.....	M-3
1 Introduction.....	M-5
1.1 Background	M-5
1.2 Purpose	M-5
1.3 Groundwater Supply.....	M-8
1.4 CNMI Bureau of Environmental and Coastal Quality	M-8
1.5 Commonwealth Utilities Corporation	M-8
1.5.1 Wells.....	M-11
1.5.2 Storage.....	M-12
1.5.3 Distribution System.....	M-13
1.6 Francisco Manglona Borja/Tinian International Airport.....	M-14
1.7 U.S. Agency for Global Media.....	M-14
1.8 Tinian Mayor’s Office.....	M-15
2 Existing Water System	M-16
2.1 Existing Water Demands.....	M-16
2.2 Water Quality and Compliance with Regulatory Standards	M-16
2.2.1 National Primary Drinking Water Standards	M-16
2.2.2 National Secondary Drinking Water Standards	M-17
2.2.3 Treatment.....	M-17
3 Water Demands for Proposed Action	M-18
3.1 Potable Water Demands Within the Military Lease Area.....	M-18
3.1.1 Design Population	M-18
3.1.2 Domestic Demands.....	M-18
3.1.3 Industrial Demands: Operation	M-19
3.1.4 Industrial Demands: Construction.....	M-19
3.1.5 Average Annual Water Demand	M-19
3.2 Potable Water Demands Outside the Military Lease Area.....	M-20
3.2.1 Domestic Demands.....	M-20
3.2.2 Industrial Demands: Operation	M-21
3.2.3 Industrial Demands: Construction.....	M-21
3.2.4 Average Annual Water Demand	M-21
3.3 Non-Potable Water Demands	M-22
3.3.1 Construction Water (Well M-21)	M-22
3.3.2 North Field Wells	M-22
3.3.3 U.S. Air Force’s Tinian Divert Infrastructure Improvements	M-22
3.3.4 U.S. Air Force’s North Field Rehabilitation	M-22
4 New Water Infrastructure	M-23

4.1	Options Evaluated	M-23
4.1.1	Option A, Connection to Commonwealth Utilities Corporation.....	M-23
4.1.2	Option B, Construct Separate Water Infrastructure	M-23
4.1.3	Option C, Interconnection Between Water Systems	M-23
4.2	Base Camp Water Infrastructure	M-24
4.2.1	Design Flow	M-24
4.2.2	Groundwater Wells.....	M-26
4.2.3	Water Treatment.....	M-26
4.2.4	Storage Requirements.....	M-26
4.2.5	Booster Pump Station.....	M-27
4.3	North Field Water Infrastructure.....	M-27
4.4	Aircraft Shelter Water Infrastructure	M-27
5	Summary.....	M-28
5.1	New Water Infrastructure.....	M-28
5.2	Commonwealth Utilities Corporation	M-28
5.3	Groundwater Impacts	M-28
6	References.....	M-30
	Attachment A February 2016 Meeting Minutes	M-33
	Attachment B Additional Unified Facilities Criteria Distribution	
	System Requirements	M-35
	GROUNDWATER MODELING TECHNICAL MEMORANDUM	M-39
1	Introduction.....	M-41
1.1	Background	M-41
1.2	Purpose	M-41
1.3	Scope of Study.....	M-42
2	Existing and Proposed Water Systems	M-45
2.1	Existing Wells	M-45
2.1.1	Current Potable Supply Wells	M-45
2.1.2	Existing Non-potable Supply Wells.....	M-46
2.1.3	Existing Monitoring Wells	M-46
2.1.4	CJMT Proposed Action Water Wells.....	M-48
3	Water Demands for Proposed Action	M-50
4	Groundwater and Geology.....	M-51
4.1	Groundwater Supply.....	M-51
4.1.1	Physical Environment of Tinian.....	M-51
4.1.2	Topography	M-51
4.1.3	Climate	M-52
4.1.4	Geology	M-54
4.2	Groundwater Resources of Tinian.....	M-57

4.2.1	Overview	M-57
4.2.2	Hydrogeology	M-58
4.3	Water Quality	M-59
5	Modeling	M-63
5.1	Modeling Approach.....	M-63
5.1.1	Previous Modeling Effort.....	M-63
5.1.2	Model Selection.....	M-63
5.1.3	Model Construction.....	M-64
5.2	Model Design	M-64
5.2.1	Grid and Layering	M-64
5.2.2	Boundary Conditions.....	M-66
5.2.3	Hydraulic Parameters	M-69
5.3	Flow Model Calibration	M-69
5.3.1	Overview	M-69
5.3.2	Steady State.....	M-69
5.4	Model Scenarios	M-77
5.5	Model Results.....	M-80
5.6	Groundwater Flow Directions	M-82
5.7	Effects of Sea Level Rise	M-101
5.8	Sustainable Yield vs. Sustainable Management of Aquifers	M-101
5.9	Model Limitations and Uncertainties	M-102
5.10	Model Summary	M-104
6	Well Siting, Installation and Operation Recommendations	M-106
6.1	Recommendations	M-106
6.2	Well Siting and Installation.....	M-107
7	Modeling Team.....	M-110
8	References.....	M-111
Attachment A Known Current and Former Wells on the Island of Tinian		M-115
WASTEWATER ANALYSIS.....		M-121
1	Purpose.....	M-123
1.1	Description of Proposed Wastewater Infrastructure	M-123
1.1.1	Base Camp.....	M-123
1.1.2	Port of Tinian.....	M-123
1.1.3	Francisco Manglona Borja/Tinian International Airport.....	M-123
1.1.4	Other Facilities	M-123
1.2	Commonwealth of the Northern Mariana Islands Wastewater Regulations	M-124
1.2.1	Individual Wastewater Disposal System Regulations.....	M-124
1.2.2	Other Wastewater Treatment System Regulations.....	M-124
1.3	Existing Wastewater Infrastructure	M-124

1.3.1	Existing Individual Wastewater Disposal System Infrastructure.....	M-124
1.3.2	Existing Other Wastewater Treatment System Infrastructure.....	M-126
1.4	Proposed Wastewater Demand and Wastewater Infrastructure	M-128
1.4.1	Design Population	M-128
1.4.2	Portable Vehicle Wash Facility.....	M-128
1.4.3	Proposed Wastewater Demand.....	M-128
1.4.4	Proposed Wastewater Infrastructure	M-129
1.5	Vehicle Maintenance.....	M-130
1.6	Summary	M-130
2	References.....	M-131
	SOLID WASTE AND HAZARDOUS WASTE STUDY	M-133
1	Introduction.....	M-135
1.1	Purpose	M-135
1.2	Study Goals and Objectives	M-135
2	Existing and Planned CNMI Waste Disposal Options	M-137
2.1	Tinian Puntan Diablo Disposal Facility	M-138
2.2	Proposed Atgidon Landfill	M-139
2.3	Marpi Landfill	M-139
2.4	Tinian Transfer Station.....	M-140
2.5	Construction and Demolition Waste	M-141
2.6	Green Waste	M-141
2.7	Hazardous, Industrial, Universal Wastes and E-Wastes	M-141
3	Proposed Action Waste Generation and Characterization.....	M-142
3.1	Solid Waste.....	M-142
3.1.1	Construction Waste	M-143
3.1.2	Green Waste	M-147
3.1.3	Hazardous, Industrial, Universal Wastes and E-Wastes	M-149
4	Proposed Action Waste Generation and Characterization— Training Operations	M-151
4.1	Solid Waste.....	M-152
4.1.1	Solid Waste Generation Rates.....	M-152
4.1.2	Solid Waste Composition and Diversion	M-152
4.1.3	Solid Waste Quantities	M-154
4.1.4	Construction Waste	M-158
4.1.5	Green Waste	M-159
4.1.6	Hazardous Waste, Industrial, Universal Wastes, and E-Wastes	M-159
5	Solid and Hazardous Waste Management Disposal Options.....	M-160
5.1	Solid Waste Management Requirements	M-161
5.2	Impacts to Existing and planned Solid Waste Management Facilities	M-162

5.2.1	Tinian Puntan Diablo Landfill.....	M-162
5.2.2	Marpi Landfill	M-163
5.2.3	Tinian Transfer Station.....	M-163
5.3	Incineration.....	M-163
5.4	Hazardous, Industrial, Universal, and Electronic Waste.....	M-165
6	Regulatory Setting	M-166
6.1	Commonwealth of the Northern Mariana Islands	M-166
6.1.1	Bureau of Environmental and Coastal Quality.....	M-166
6.1.2	Coastal Resources Management.....	M-166
6.1.3	Division of Fish and Wildlife	M-167
6.1.4	Historic Preservation Office	M-167
6.2	United States Government.....	M-168
6.2.1	United States Environmental Protection Agency	M-168
6.2.2	Federal Aviation Administration.....	M-168
7	References.....	M-170
	STORMWATER STUDY	M-171
1	Introduction.....	M-173
1.1	Purpose	M-173
2	Regulatory Framework	M-174
2.1	Energy Independence and Security Act of 2007 Section 438	M-174
2.2	Technical Guidance for the Energy Independence and Security Act Section 438 Implementation	M-174
2.3	Department of the Navy Low Impact Development Policy for Stormwater Management.....	M-174
2.4	Department of Defense Implementation of Storm Water Requirements under the Energy Independence and Security Act Section 438	M-175
2.5	Unified Facilities Criteria 3-201-01, Civil Engineering.....	M-175
2.6	Unified Facilities Criteria 3-210-10, Low Impact Development	M-175
2.7	National Pollutant Discharge Elimination System Permit Administration	M-175
2.8	CNMI and Guam Stormwater Management Manual	M-175
2.9	Range Environmental Vulnerability Assessment.....	M-177
3	Existing Conditions.....	M-178
3.1	Topography	M-178
3.2	Existing Slope.....	M-178
3.3	Soils	M-180
3.4	Climate and Hydrology	M-180
4	Stormwater Considerations	M-182
4.1	Assumptions	M-182
4.2	Depressional Areas.....	M-183

4.3	Protected Surface Waters	M-183
4.4	Fault Lines.....	M-183
5	Water Quantity Analysis.....	M-184
5.1	Digital Elevation Model Development.....	M-184
5.2	Flow Path Determination and Sub-basin Delineation	M-185
5.3	Land Use and Land Cover.....	M-185
5.4	Tinian Curve Number Values.....	M-187
5.5	Initial Abstraction/Storage	M-187
5.6	Time of Concentration.....	M-187
5.7	Design Storm Frequency	M-188
5.8	Design Rainfall Depths and Distribution	M-188
5.9	Results of Analysis.....	M-189
6	Stormwater Best Management Practices/Integrated Management Practices	M-191
6.1	Stormwater Management Practices	M-191
6.2	Water Quality/Low Impact Development	M-191
6.3	Water Quality and Recharge Volumes.....	M-192
6.4	Low Impact Development Application	M-194
6.5	Integrated Management Practices	M-194
6.6	Base Camp Treatment Options.....	M-194
6.6.1	Multi-Purpose Maneuver Range and Explosives Training Range Treatment...	M-195
7	Conclusions.....	M-197
8	References.....	M-198
	Attachment A Supporting Calculations.....	M-201
	Attachment A.1 Base Camp HydroCAD Results.....	M-203
	Attachment A.2 ETR and MPMR HydroCAD Results.....	M-205
	Attachment A.3 Calculations	M-207
	ELECTRICAL SYSTEM ANALYSIS	M-209
1	Purpose.....	M-211
1.1	Background	M-211
2	Existing Electrical System on Tinian	M-214
2.1	Commonwealth Utilities Corporation Island-wide System.....	M-214
3	Estimated Electrical Demand and Proposed Electrical Infrastructure with CJMT Action.....	M-216
3.1	Power Demand	M-216
3.2	Medium Voltage Power Distribution	M-218

3.2.1 Electrical Distribution System..... M-218
3.3 Quantities – Underground Distribution..... M-220
4 References..... M-221
Attachment A Calculations M-223
Appendix N CZMA FEDERAL CONSISTENCY
DETERMINATION N-1

LIST OF FIGURES

POTABLE WATER STUDY

Figure 1 Island of Tinian – LocationM-6
Figure 2 Island of Tinian – Military Lease Area BoundariesM-7
Figure 3 Tinian Groundwater Wells, Elevation, and Flow Direction.....M-9
Figure 4 Commonwealth Utilities Corporation Existing Potable Water SystemM-10
Figure 5 Maui Well No. 2 Pump HouseM-11
Figure 6 Maui Well No. 2 Pump EquipmentM-11
Figure 7 Carolinas Tank 1 (0.50 Million Gallons)M-12
Figure 8 Carolinas Tank 2 (0.50 Million Gallons)M-12
Figure 9 Marpo Tank (0.25 Million Gallons) in 2013M-13
Figure 10 Marpo Tank (0.25 Million Gallons) in 2024M-13
Figure 11 Water Tank and Booster Pump Station at Francisco Manglona Borja/Tinian
International AirportM-14
Figure 12 Non-potable Water Storage Tank at U.S. Agency for Global Media Facility on Tinian
.....M-14
Figure 13 Water Infrastructure Included in Proposed Action.....M-25

GROUNDWATER MODELING TECHNICAL MEMORANDUM

Figure 1 Island of Tinian – LocationM-43
Figure 2 Island of Tinian – Military Lease Area BoundariesM-44
Figure 3 Tinian Existing Wells.....M-47
Figure 4 Tinian Future Wells.....M-49
Figure 5 Tinian Physiographic AreasM-53
Figure 6 Tinian Generalized Surficial Geology.....M-55
Figure 7 Tinian Geologic Cross SectionsM-56
Figure 8 Generalized Depiction of a Freshwater Lens above Saltwater.....M-57
Figure 9 Groundwater Model Domain.....M-65
Figure 10 Model Cross Sections.....M-67
Figure 11 Model BoundariesM-68
Figure 12 Model Head Residuals.....M-73

Figure 13 Scatter Plot of Observed Heads vs. Simulated HeadsM-74
Figure 14 Model Hydraulic Conductivity Values and Distribution in Model Layer 1.....M-75
Figure 15 Model Recharge.....M-76
Figure 16.1 Modeled Chloride Concentrations for Layer 1 – Scenario 1.....M-83
Figure 16.2 Modeled Chloride Concentrations for Layer 2 – Scenario 1.....M-84
Figure 16.3 Modeled Chloride Concentrations for Layer 3 – Scenario 1.....M-85
Figure 17.1 Modeled Chloride Concentrations for Layer 1 – Scenario 2.....M-86
Figure 17.2 Modeled Chloride Concentrations for Layer 2 – Scenario 2.....M-87
Figure 17.3 Modeled Chloride Concentrations for Layer 3 – Scenario 2.....M-88
Figure 18.1 Modeled Chloride Concentrations for Layer 1 – Scenario 3.....M-89
Figure 18.2 Modeled Chloride Concentrations for Layer 2 – Scenario 3.....M-90
Figure 18.3 Modeled Chloride Concentrations for Layer 3 – Scenario 3.....M-91
Figure 19.1 Modeled Chloride Concentrations for Layer 1 – Scenario 4.....M-92
Figure 19.2 Modeled Chloride Concentrations for Layer 2 – Scenario 4.....M-93
Figure 19.3 Modeled Chloride Concentrations for Layer 3 – Scenario 4.....M-94
Figure 20.1 Modeled Chloride Concentrations for Layer 1 – Scenario 5.....M-95
Figure 20.2 Modeled Chloride Concentrations for Layer 2 – Scenario 5.....M-96
Figure 20.3 Modeled Chloride Concentrations for Layer 3 – Scenario 5.....M-97
Figure 21 Modeled Groundwater Heads and Groundwater Flow Directions – Scenario 1M-98
Figure 22 Modeled Groundwater Heads and Groundwater Flow Directions – Scenario 3M-99
Figure 23 Modeled Groundwater Heads and Groundwater Flow Directions – Scenario 5M-100

WASTEWATER ANALYSIS

Figure 1 Existing Individual Wastewater Disposal System at USAGMM-125
Figure 2 Existing Individual Wastewater Disposal System near Camp Tinian.....M-126
Figure 3 Entrance to the Tinian Dynasty Hotel and CasinoM-127
Figure 4 Other Wastewater Treatment System at Tinian Diamond Hotel and Casino.....M-127

STORMWATER STUDY

Figure 1 Island of Tinian – Physiographic Regions.....M-179
Figure 2 Island of Tinian – Hydrologic Soil GroupsM-181
Figure 3 Land Cover on the Island of Tinian.....M-186

ELECTRICAL SYSTEM ANALYSIS

Figure 1 Island of Tinian – LocationM-212
Figure 2 Island of Tinian – Military Lease Area BoundariesM-213
Figure 3 Existing Electrical Distribution SystemM-217
Figure 4 Proposed Electrical Distribution System.....M-219

LIST OF TABLES

POTABLE WATER STUDY

Table 1. Commonwealth Utilities Corporation Water Production from Maui Well No. 2M-16
Table 2. Commonwealth Utilities Corporation Billed Water Demand.....M-16
Table 3. Chloride Concentrations at Maui Well No. 2M-17
Table 4. Average Day Domestic Demand Within the Military Lease Area Under Alternative 1
.....M-18
Table 5. Average Annual Water Demands Within the Military Lease Area Under Alternative
1M-20
Table 6. Average Day Domestic Demand on Commonwealth Utilities Corporation Water System
Under Alternative 1.....M-20
Table 7. Summary of Existing and Proposed Water Demands on Commonwealth Utilities
Corporation Under Alternative 1M-21
Table 8. Summary of Average Annual Water Demands on Tinian.....M-29

GROUNDWATER MODELING TECHNICAL MEMORANDUM

Table 1. Summary of Average Future Annual Water Demands on TinianM-50
Table 2. Chloride Concentrations at Maui Well No. 2M-60
Table 3. Commonwealth Utilities Corporation Water Production from Maui Well No. 2M-62
Table 4. Measured and Calculated Water LevelsM-71
Table 5. Calculated Differences Between Measured and Modeled ResultsM-72
Table 6. Statistics of 2025 AECOM (Eight-Layer) Model.....M-72
Table 7. Pumping Rates for Scenarios 1 through 5M-79
Table 8. Predicted Chloride Concentrations for Scenarios 1 through 5M-80
Table 9. 2015 Aquifer Study Chloride ConcentrationsM-81
Table 10. Chloride Concentrations Observed Before and After PumpingM-81
Table 11. Model Limitations.....M-103
Table A-1. Known Current and Former Wells on the Island of Tinian.....M-117

WASTEWATER ANALYSIS

Table 1. Peak Proposed Wastewater DemandM-128

SOLID AND HAZARDOUS WASTE STUDY

Table 1. Proposed Action Project Phasing.....M-136
Table 2. Estimated 2023 Tinian Puntan Diablo Disposal TonnageM-139
Table 3. Estimated Existing (2023) Marpi Landfill Disposal Tonnage.....M-140
Table 4. Estimated Solid Waste Generation – Construction PhaseM-143
Table 5. Projected Construction Waste Generation.....M-143
Table 6. Estimated Construction and Demolition Composition for New Structures/Buildings –
Construction Phase.....M-145

Table 7. Estimated Construction and Demolition Composition for New Concrete Surfaced Areas – Construction Phase.....	M-146
Table 8. Estimated Construction and Demolition Waste Generation, Diversion and Disposal – Construction Phase.....	M-146
Table 9. Projected Green Waste Generation During Construction.....	M-147
Table 10. Estimated Annual Green Waste Generation - Construction Phase.....	M-149
Table 11. Tinian Training Area - Solid Waste Composition During Training.....	M-152
Table 12. Tinian Training Area – Estimated Recyclable Diversion Rates.....	M-154
Table 13. Alternative 1 Training Events, Duration, Frequency and Projected Headcount	M-155
Table 14. Training Event Frequency and Personnel Headcount.....	M-155
Table 15. Maximum Solid Waste Generation (per year).....	M-156
Table 16. Solid Waste Generation (per day).....	M-157
Table 17. Solid Waste Generation	M-158
Table 18. Expended Ammunition Casing Metals.....	M-158
Table 19. Projected Construction and Demolition Waste Generation During Training Operations	M-159
Table 20. Existing Disposal Capacity vs. Required Capacity	M-162

STORMWATER STUDY

Table 1. Curve Numbers Used for Post-project Land Cover and Soil on Tinian.....	M-187
Table 2. Rainfall Data per Design Storm.....	M-188
Table 3. HydroCAD Stormwater Parameters	M-190
Table 4. HydroCAD Stormwater Results	M-190
Table 5. Water Quality Volumes	M-193
Table 6. Recharge Volumes.....	M-194

POTABLE WATER STUDY

Table 1. Electrical Power System Peak Demand and Capacity.....	M-216
Table 2. Duct Bank Quantities.....	M-220
Base Camp Load Schedule	M-225
Duct Bank - Quantities.....	M-226
Electrical Distribution System – Quantities.....	M-227

APPENDIX M UTILITY STUDIES

This page intentionally left blank.

**ELECTRICAL SYSTEM ANALYSIS
IN SUPPORT OF THE
COMMONWEALTH OF THE NORTHERN MARIANA
ISLANDS
JOINT MILITARY TRAINING ENVIRONMENTAL
IMPACT STATEMENT**



Department of the Navy
Naval Facilities Engineering Systems Command, Pacific
258 Makalapa Drive, Suite 100
JBPHH HI 96860-3134

June 2026

This page is intentionally left blank.

1 PURPOSE

The purpose of this memorandum is to provide technical background and analysis of power distribution in support of the Commonwealth of the Northern Mariana Islands (CNMI) Joint Military Training Final Environmental Impact Statement (EIS).

1.1 BACKGROUND

The islands of the CNMI are strategically located in the United States (U.S.) Department of Defense (DoD) Indo-Pacific area of operations, as shown in Figure 1. Figure 2 shows the Military Lease Area on Tinian where the U.S. military has trained for several decades.

The Proposed Action would support the ongoing and evolving training requirements of U.S. Armed Forces forward deployed to the Western Pacific, and of U.S. allies and partners, specifically for distributed operations training within the Military Lease Area on Tinian. Proposed training events would include both ground and aviation training within the Military Lease Area.

Non-live-fire offensive and defensive training actions would continue to be conducted in the Military Lease Area with an increase in existing land-based training events, including both ground and aviation training, which are the same or similar to those currently being conducted on Tinian.

Live-fire training would be conducted at two ranges that would be developed within the Exclusive Military Use Area:

- **Multi-Purpose Maneuver Range.** A live-fire range occupying approximately 200 acres at the northern tip of Tinian to support platoon-size live-fire and maneuver, including three surface radar facilities.
- **Explosives Training Range.** A live-fire range on approximately 2.5 acres for the employment of demolitions and military explosives in support of offensive and defensive training events.

The following are also included in the Proposed Action to support training events:

- Establishment of 13 Landing Zones, areas cleared of vegetation to 6–8 inches, and associated access roads to conduct training events and to provide staging, bivouac, and gathering and rendezvous areas.
- Ground and aviation improvements at North Field, including establishment of a drop zone and the placement of a metal airfield surface.
- Construction and operation of a Base Camp.
- Clearance and improvements of roads within the Military Lease Area.



Figure 1 Island of Tinian – Location



Figure 2 Island of Tinian – Military Lease Area Boundaries

2 EXISTING ELECTRICAL SYSTEM ON TINIAN

2.1 COMMONWEALTH UTILITIES CORPORATION ISLAND-WIDE SYSTEM

The Commonwealth Utilities Corporation, a public corporation, owns the existing island-wide electrical distribution system on Tinian. Telesource CNMI, Inc., operates and maintains the system under an Independent Power Provider agreement with the Commonwealth Utilities Corporation. The status of the agreement and whether the Commonwealth Utilities Corporation would inherit the workforce and take over operations, has yet to be confirmed. This would still allow the Commonwealth Utilities Corporation to have flexibility to continue contracting certain items from Telesource CNMI, Inc., if needed. This existing system includes several electrical generation units and distribution infrastructure, which consists of overhead and underground distribution lines, power poles, utility holes, transformers, substations, and meters used to provide and measure power to island customers (Information cited in Cardno GS).

The existing electrical generation system at the powerplant consists of the following components:

- Four 4.16 kilovolt, 2.5 megawatt diesel generators
- Two 4.16 kilovolt, 5.5 megawatt diesel generators
- Two exhaust stacks:
 - One 90-foot tall stack to service four 2.5 megawatt generators
 - One 175-foot tall stack to service two 5.5 megawatt generators
- An aboveground fuel delivery pipeline from the existing diesel fuel storage tank at the Port of Tinian to a diesel storage tank, which is adjacent to the power plant facility
- Expansion capability for two additional 5.5 megawatt diesel generators (including space inside the existing generator building and tie-in points to the existing exhaust stack)

Data collected in the field indicated an installation date of 1999 for the generators.

The location, configuration, and electrical capacity are essential details for the evaluation of the Tinian Power Plant. The Tinian Power Plant is a single generation facility near the coast outside of San Jose at 25 feet above mean sea level. The powerplant has a total generator operating capacity of 18.2 megawatt with available capacity of 12.70 megawatt considering the maintenance scenario of the largest generator to accommodate additional loads. The powerplant's capacity could be expanded because it has space for two additional 5.5 megawatt generators that would provide an additional 11 megawatt to the system capacity, if installed; this would provide a total generator operating capacity of 29.2 megawatt and an available capacity of 24.7 megawatt. The 4,160-volt output from each of the six diesel generators feed the 1200A synchronizing switchgear that in turn feeds step-up transformers.

The step-up transformers increase the 4,160 volt up to 13.8 kilovolt for power distribution, except for Feeder 2, which distributes power at 4,160 volt. This feeder was anticipated to be upgraded from 4,160 volt to 13.8 kilovolt by 2024, and its current status is unknown. The island-wide electrical distribution consists of four medium voltage feeders that originate from the Commonwealth Utilities Corporation plant. Feeder 1 was identified as offline and loads transferred to Feeder 2. Feeders 2 and 3 support most of the island. Feeder 4 is a dedicated feeder that serves

the former U.S. Agency for Global Media (USAGM) facility (Department of the Navy [DON] 2018).

See Figure 3 for existing feeder distribution and designations.

Much of the existing island-wide electrical distribution system is overhead except for lines within the vicinity of the airfield runways. The existing overhead power distribution on the island has been replaced with concrete poles after impacts from Typhoon Yutu in 2018. The extent of how much of the overhead line distribution has been replaced to date has yet to be determined.

A 2017 Tinian Unscheduled Power Outages report received during the site investigation, revealed the following outages:

- 2015 – 11 Emergency Outages
- 2016 – 6 Emergency Outages

No additional information as to the cause of the outage events is known.

3 ESTIMATED ELECTRICAL DEMAND AND PROPOSED ELECTRICAL INFRASTRUCTURE WITH CJMT ACTION

3.1 POWER DEMAND

The existing system capacity at the Tinian power shall not exceed 12.70 MW. Proposed operations would add an estimated 0.146 megawatt of peak electricity demand to operate facilities and supporting infrastructure and equipment. The additional electrical demand loads on the proposed operations include the three surface radar facilities, which may alternatively be powered by temporary or permanent generators. This increase in peak demand accounts for 1.15 percent of total island-wide/Commonwealth Utilities Corporation system capacity. Table 1 provides a summary of existing and proposed electrical demands relative to the existing electrical system capacity. With this added electrical demand, the system maintains a 9.55 megawatt capacity reserve, which is 75.2 percent of the total system capacity (see Attachment A for calculation details). The existing island-wide power generation facility is capable of meeting the increased power demand during the proposed operations; therefore, the impacts would be less than significant.

Table 1. Electrical Power System Peak Demand and Capacity

<i>Item</i>	<i>MW of Electricity</i>	<i>% of System Capacity</i>
Tinian Power Plant Effective Design Capacity	12.70	100
Peak Electrical Demand from Existing Customers	3.00	23.5
Additional Peak Electrical Demand from Proposed Facilities	0.146	1.15
Total Electrical Demand with Proposed Facilities	3.146	24.8
Remaining Electrical Generating Capacity with Proposed Action	9.51	75.2

Legend: % = percent; MW = megawatt.

Multiple interconnection points to the grid exist. However, a spare breaker is available that could be used for the U.S. Marine Corps (USMC) and, based on peak demand load information received for 2016 and 2017, it is recommended that the USMC be tied to the existing Feeder 4 with the former USAGM infrastructure. Further analysis and investigations and data gathering on peak demand readings are required to validate this recommendation.

Demand load information indicated a peak demand load of 1.4 megawatt on Feeder 4; the demand from the proposed facilities is approximately 0.146 megawatt. The addition of the 0.146 megawatt load on Feeder 4 is insignificant and would not require the installation of a dedicated feeder.



Figure 3 Existing Electrical Distribution System

3.2 MEDIUM VOLTAGE POWER DISTRIBUTION

Power and communications would be required at the proposed facilities, surface radars, and communications towers. Power would originate from the existing Commonwealth Utilities Corporation powerplant. Feeder taps on the existing 13.8-kilovolt USAGM overhead Feeder 4 would be required to support the facilities, surface radars, and communications towers.

Communications would originate from the Tinian commercial internet service provider hub, east of the Commonwealth Utilities Corporation power plant.

The electrical feeder and communications lines would be routed to the proposed facilities and surface radar towers via underground distribution. Surface radar towers supported via underground feeders would provide less maintenance, increased reliability and less cost in operating than if were supported by generators. However, initial cost of using generators would be substantially less. The underground distribution would include concrete-encased duct banks and medium-voltage utility holes. Utility holes would be installed at each change in direction and spaced not greater than 400 feet on straight runs as indicated per Unified Facilities Criteria 3-550-01 (DoD 2019). Where tapped from the existing overhead line, additional overhead power equipment and a riser would be required for the proposed distribution. Additional coordination with Commonwealth Utilities Corporation would be required for any outages during cutover of the 13.8-kilovolt feeder to the proposed operations.

Figure 4 reflects the proposed routing of the underground distribution for both power and communications. Further site investigation is required to verify the exact routing of the underground duct bank and utility hole locations to support the proposed operations. Duct bank configurations, utility hole sizes, and exact cable termination points would be deferred and determined during the detailed design effort.

3.2.1 Electrical Distribution System

The existing 13.8-kilovolt Commonwealth Utilities Corporation overhead line running north along 8th Street would be tapped at the power poles to provide underground lateral feeds to the proposed operations, except for the Base Camp and the communications towers.

The demobilization of the former USAGM facilities would allow reuse of the existing medium voltage distribution to support the Base Camp. An existing medium voltage switchgear would remain in place to be used from site electrical distribution. It was noted that the existing switchgear requires repair to the existing bus. The extent of the repair to the switchgear is currently unknown.

The feeder and communications lines would continue underground to the north approximately 2,000 feet east of Runway Baker to feed the two surface radar locations, the Multi-Purpose Maneuver Range, AHA1, and wells.

The feeder would also branch at 86th Street due west to support Base Camp Well Field – Option A or due east towards Base Camp Well Field – Option B, the preferred option.

A recently installed extension of Feeder 4 located north of the Francisco Manglona Borja/Tinian International Airport as part of the Tinian Divert Infrastructure Improvements would be tapped and routed underground to feed the proposed aircraft shelter.



Figure 4 Proposed Electrical Distribution System

3.3 QUANTITIES – UNDERGROUND DISTRIBUTION

Below is a summary of the anticipated quantities of utility holes, trenching, and backfill for both the electrical and communications underground distribution systems.

This underground distribution includes approximately 85,665 linear feet of underground duct bank with 121 electrical utility holes and 221 communication utility holes. Table 2 provides the estimated quantity of duct bank (excavation, backfill, and concrete).

Table 2. Duct Bank Quantities

<i>Type</i>	<i>Total + 15% Contingency (Cubic Yards)</i>
Excavation	36,037
Concrete	14,299
Backfill	18,818

Legend: % = percent.

Impacts to the existing electrical and communication systems on the neighboring Island of Saipan have been explored for training activities. No training activities would be conducted at the USAGM site on Saipan. Military traffic would be limited to occasional inspection and maintenance of the communication antenna. Replacement of the existing high-powered shortwave transmission station tower with lower-powered Radio Frequency antennas would either offset or result in a net increase of the existing electrical distribution capacity. Consequently, there would be no impact to the electrical distribution at this site on Saipan.

4 REFERENCES

DON. 2018. *Electrical Study Update V2a1 Final in Support of the Commonwealth of the Northern Mariana Islands Joint Military Training Environmental Impact Statement/Overseas Environmental Impact Statement*. JBPHH, HI. Prepared for NAVFAC Pacific.

DoD. 2019. *Unified Facilities Criteria (UFC), Exterior Electrical Power Distribution*. UFC 3-550-01. Including Change 3. November 1.

This page is intentionally left blank.

ATTACHMENT A CALCULATIONS

This page is intentionally left blank.

Base Camp Load Schedule

Tinian Base Camp Structures

<i>Facility Name</i>	<i>Unit of Measure</i>	<i>Quantity / Size</i>	<i>Watt/ SF</i>	<i>Watt/ EA</i>	<i>Calculate d (kW)</i>	<i>Calculate d (kVA)</i>	<i>Total kVA inc. 25% spare</i>	<i>Xfmr size (kVA)</i>	<i>Total Demand (kVA)</i>	<i>Assumption & Notes</i>
Outdoor Services										
Ammunition Holding Area (AHA-1)	SF	100	2.19		0.22	0.27	0.34	7.5		
Bivouac Concrete Pad	SF	1	0		0.00	0.00	0.00	0		Electrical needs provided by generators
Biosecurity/Washrack	SF	5,400	0.15		0.81	1.01	1.27	7.5		
Facilities										
Administration/HQ Building	SF	2,115	24		50.76	63.45	79.31	112.5		
Range Control Building (Admin)	SF	4,155	7.5		31.16	38.95	48.69	75		
Base Camp	SF	1	0		0.00	0.00	0.00	0		Electrical needs provided by existing USAGM service
Warehouse	SF	18,000	2		36.00	45.00	56.25	75		
Exercise Control (Training Unit Operational Facility)	SF	1,000	6		6.00	7.50	9.38	15		
Restroom/Showers	SF	5,700	2		11.40	14.25	17.81	25		
Miscellaneous Facilities										
Surface Radar 1	EA	1		12500.00	12.50	15.63	19.53	25		
Surface Radar 2	EA	1		12500.00	12.50	15.63	19.53	25		
Communications Towers	EA	3	0		0.00	0.00	0.00	0		Electrical needs provided by existing USAGM service
Hardened Aircraft Shelter	SF	20,020	6		120.12	150.15	187.69	225		
Well Field Monitor	EA	2		750.00	1.50	1.88	2.34	7.5		(2) Sensor, (1) Data Logger, Aux. Equip., Lighting
Fueling/Fuel Tanks	SF	1,500	0.5		0.75	0.94	1.17	7.5		
								607.5	182.25	Demand kVA based on 30% of the sum of all transformer ratings
									145.8	Demand kW with 0.8 PF

Legend: % = percent; Admin = administration; USAGM = United States Agency for Global Media; Aux. = auxiliary; EA = each; HQ = headquarters; kVA = kilovolt ampere; kW = kilowatt; PF = power factor; SF = square foot; Xfmr = transformer.

Duct Bank - Quantities

		<i>L (FT.)</i>	<i>W (FT.)</i>	<i>D (FT.)</i>	<i>Cross Section Area (FT.)</i>	<i>CU. FT.</i>	<i>CU. YD</i>	<i>All Conduit Areas</i>	
Power/Comm	Excavation	53138.56	3.50	3.83	13.41	712322.34	26382.31	sqin.	Sqft.
	Concrete	53138.56	3.50	1.83	5.30	281678.63	10432.54	95.00	0.66
	Backfill	53138.56	3.50	2.00	7.00	371969.89	13776.66	64.00	0.44
								159.00	1.10
Comm	Excavation	45376.48	1.50	3.83	5.75	260687.89	9655.11	<i>Comm Conduit Areas</i>	
	Concrete	45376.48	1.50	1.83	2.30	104391.12	3866.34	sqin.	Sqft.
	Backfill	45376.48	1.50	2.00	3.00	136129.44	5041.83	64.00	0.44
								64.00	0.44
TOTALS									
							<i>CUBIC YARDS</i>		
Total + 15% Contingency							Excavation	36037.42	
							Concrete	14298.88	
							Backfill	18818.49	

Legend: % = percent; Comm = communications; CU. FT. = cubic foot; CU. YD = cubic yard; D = depth; FT. = foot or feet; L = length; squin. = square inch; Sqft. = square foot; W = width.

Electrical Distribution System – Quantities

Route Segments	Connecting Segment Numbers	Route Description	Routing Type	Length (Feet)	Number of Poles @135' Spacing	Number of Manholes @400' Spacing	Length (Meters)	Notes	
Segment 1	A to B	Existing OH electrical to Tinian Powerplant	Existing Electrical (OH)	9,823			2,994	Tinian Powerplant to Airport, existing poles.	
Segment 2	B to C	Existing UG electrical to Tinian Powerplant	Existing Electrical (UG)	2,810		8	856	West of Tinian International Airport clearance zone (west), required to be underground.	
Segment 3	C to D	Existing OH electrical to USAGM	Existing Electrical (OH), Proposed Comm (OH)	17,392			5,301	Existing USAGM Feeder from Airport to Base Camp would connect wells in Well Option A Site. Comm installed on existing OH poles.	
Segment 4	E to F	Proposed UG electrical and comm lines	Proposed Elec/Comm (UG)	11,205		29	3,415	Base Camp to Surface Radar Site 1.	
Segment 5	G to H	Proposed UG electrical and comm lines	Proposed Elec/Comm (UG)	13,381		34	4,079	Unai Chulu Road to Ushi Point Road.	
Segment 6	H to J	Proposed UG electrical and comm lines	Proposed Elec/Comm (UG)	5,260		14	1,603	Proposed UG from 8th Avenue To North Comm Tower.	
Segment 7	H to K	Proposed UG electrical and comm lines	Proposed Elec/Comm (UG)	4,763		13	1,452	Ushi Point Road to AHA 1 (lighting, comms), also connects MPMR water tanks/wells.	
Segment 8	L to M	Proposed UG electrical and comm lines	Proposed Elec/Comm (UG)	11,599		30	3,535	Proposed UG elec/comm from 8th Avenue to Well Field Option B (connects wells).	
Segment 9	L to O	Proposed UG comm lines	Proposed Comm (UG)	26,236		67	7,997	Base Camp to Broadway (inside MLA Boundary).	
Segment 10	N to P	Proposed UG comm lines	Proposed Comm (UG)	13,222		34	4,030	Broadway MLA to Commercial Internet Service Provider (San Jose).	
Total Comm OH Poles					0				
Total Elec OH Poles					0				
Total # Poles					0				
Total Comm Manholes					221				
Total Elec Manholes					121				
Total # of Manholes					342				
MH Spacing					400				
Pole Spacing					135				

Legend: ADN = area distribution node; AHA = Ammunition Holding Area; Comm = communications; Elec = electrical; MLA = Military Lease Area; MPMR = Multi-Purpose Maneuver Range; OH = overhead; UG = underground; USAGM = United States Agency for Global Media.

This page is intentionally left blank.